

NJDOT Intersection Improvement Program

Various Locations | Union and Morris Counties, NJ



Van Cleef provided roadway and traffic signal inspection on this \$1.9M substantive safety improvement to the corridor and intersections project with a focus on all signalized intersections within the project limits. Intersection improvements with high visibility crosswalk striping, new traffic signal equipment and signal back plates. Construction items supervised and inspected included; ADA compliant pedestrian curbs and ramps, warning surface pads, signal heads, push-buttons, signal timings (including Leading Pedestrian Intervals), Pedestrian Detection System, median crash cushions, corner radius treatment at select intersections, pedestrian-scale lighting corridor improvements. Reconstruction of sidewalk at select locations, high-friction asphalt at select locations to reduce vehicle stopping distance and drainage improvements to address ponding and standing water issues.

CLIENT CONTACT

New Jersey Department
Of Transportation
Region North
Mt. Arlington, NJ

PROJECT HIGHLIGHTS

- 🔗 NJDOT Client-Capital Programs
- 🔗 Roadway Construction
- 🔗 ADA Improvements
- 🔗 Road Safety Improvements
- 🔗 Utility Relocations
- 🔗 MPT Plans
- 🔗 Pedestrian Safety
- 🔗 Crosswalks
- 🔗 Traffic Signal Improvements